



NOTES:

- 4'-6" x 8'-6" x 6'-6" NOMINAL INSIDE DIMENSIONS PRECAST MANHOLE WITH 30" COVER.
- DESIGN LOAD: H-20 FULL TRAFFIC WITH 13 INCHES TO 4 FEET SOIL COVER TO TOP OF SLAB. WATER TABLE BELOW BASE OF VAULT.
- ENTIRE VAULT ASSEMBLY AND CONDUIT INSTALLATION SHALL BE CLEAN AND DRY AT TIME OF ACCEPTANCE.
- BACKFILL AROUND VAULT ASSEMBLY IN ACCORDANCE WITH SPEC SEC 31 20 00.
- FINAL MANHOLE FRAME ADJUSTMENT AND CONCRETE COLLAR INSTALLATION REQUIREMENTS, SEE (PL08-4)
- INSTALL 3' DIA x 3' DEEP DRAIN GRAVEL PACK UNDER 12" DRAIN HOLE AND COVER (CENTERED).
- INCLUDE CABLE RACKING WITH EACH MANHOLE FOR FIELD INSTALLATION.

APPROXIMATE LOCATIONS OF FIBER OPTIC VAULTS

PROJECT / VAULT ID NO.	DWG NO.	STATION
XXXXX-1	XX	XX+XX
XXXXX-2	XX	XX+XX
XXXXX-3	XX	XX+XX
XXXXX-4	XX	XX+XX
XXXXX-5	XX	XX+XX
XXXXX-6	XX	XX+XX
XXXXX-7	XX	XX+XX
XXXXX-8	XX	XX+XX
XXXXX-9	XX	XX+XX
XXXXX-10	XX	XX+XX

FIBER OPTIC VAULT ASSEMBLY

SCALE: 1/4" = 1'-0"

PL06-3 042425

