



NOTES:

1. DISTRICT SECURITY CONTRACTOR TO PROVIDE INTERCONNECTING CABLE, SITE CONTRACTOR TO PULL CABLE FROM SENSORS, DEVICES AND CONTROLS TO SECURITY SYSTEM CABINET. TWO SEPARATE SYSTEMS ARE DEPICTED IN THIS STANDARD.
2. CONDUIT FROM POWERED DOOR STRIKES, ENTRY DOOR AND GATE CARD READERS, ENTRY GATE REMOTE RELEASE AND MOTION SENSORS FROM FIELD.
3. PROVIDE CONDUIT FOR 120VAC POWER FROM LIGHTING PANEL AND FOR CAT6A TO COMMUNICATIONS CABINET SECURITY SWITCH.
4. VERIFY CONDUIT REQUIREMENTS WITH DISTRICT'S SECURITY CONTRACTOR.
5. CONDUIT FROM ENTRY DOORS, VAULT AND BASIN ACCESS HATCHES, SECURED CABINETS AND "ARMED/BYPASS KEY SWITCH" TO DISTRICT SECURITY ANNUNCIATOR CABINET.
6. PROVIDE CONDUIT AND CONDUCTOR FROM DISTRICT SECURITY ANNUNCIATOR PANEL TO PAC/PLC CABINET FOR ALARMS AND CABINET POWER.
7. VERIFY CONDUIT COUNT AND ROUTING WITH PLAN DRAWINGS AND CONDUIT AND CABLE SCHEDULES.

SITE SECURITY SYSTEMS CABINETS

NOT TO SCALE

E09-8

042622

