



NOTES:

1. ALL GROUND PLATES ARE TO BE FLUSH WITH SURFACE PENETRATED SO AS TO NOT CAUSE A TRIPPING HAZARD. IF FOR ANY REASON THE GROUND PLATE IS NOT INSTALLED FLUSH THE CONTRACTOR SHALL BE REQUIRED AT HIS EXPENSE TO: JACK-HAMMER AND REPOUR CONCRETE; REMOVE AND REINSTALL MASONRY; PAINT; GROUT; RELOCATE EQUIPMENT; PROVIDE TEMPORARY FACILITIES.
2. CONTRACTOR TO SUBMIT GROUNDING ROUTE PLAN AND DETAIL PER SPECS SEC 26 05 26 FOR LVVWD APPROVAL.

EQUIPMENT GROUNDING PLATE

NOT TO SCALE

E02-7 061119

