

## NOTES:

- SECURE AND SUPPORT LIQUIDTIGHT FLEX CONDUIT WITHIN 1' OF DEVICE BOX AND IN ACCORDANCE WITH NEC ARTICLE 350.
- 2. IF DISTRICTS SECURITY SYSTEM CONTRACTOR INSTALLS THE CAMERA MOUNT A GREATER DISTANCE THEN ALLOWED FOR LIQUIDTIGHT CONNECTIONS, THE SECURITY CONTRACTOR SHALL RELOCATE THE DEVICE BOX AND REPIPE THE RIGID CONDUIT.
- 3. CAMERA LOCATION IN ACCORDANCE WITH THE DRAWINGS.
- 4. ANCHORING THE CAMERA MOUNT BY THE DISTRICTS SECURITY SYSTEM CONTRACTOR:
  - a). EXPANSION ANCHORS FOR MASONRY, CONCRETE OR GYPSUM.
  - b). DRILL AND/OR TAP FOR STEEL OR SHEET METAL MOUNT.
  - c). SEAL ALL ANCHORS AS A APPROPRIATE FOR INSTALLATION.
  - d). ALL CAMERA MOUNT METHODS AS APPROVED BY THE ENGINEER.
- 5. 6"x6"x4" DEVICE BOX.
- 6. DISTRICT SECURITY SYSTEM CONTRACTOR TO INSTALL AND TERMINATE MAXIMUM OF 4'-6" OF LIQUIDTIGHT FLEX CONDUIT IN ACCORDANCE WITH NEC ARTICLE 350.
- 7. DISTRICT SECURITY SYSTEM CONTRACTOR TO PROVIDE ALL CABLING.

## SECURITY SYSTEM INTERIOR CEILING MOUNT CAMERA

NOT TO SCALE

E13-1

102907

FOR REFERENCE ONLY