



**NOTES:**

1. SECURE AND SUPPORT LIQUIDTIGHT FLEX CONDUIT WITHIN 1' OF DEVICE BOX AND IN ACCORDANCE WITH NEC ARTICLE 350.
2. IF DISTRICTS SECURITY SYSTEM CONTRACTOR INSTALLS THE CAMERA MOUNT A GREATER DISTANCE THEN ALLOWED FOR LIQUIDTIGHT CONNECTIONS, THE SECURITY CONTRACTOR SHALL RELOCATE THE DEVICE BOX AND REPIPE THE RIGID CONDUIT.
3. CAMERA LOCATION IN ACCORDANCE WITH THE DRAWINGS.
4. ANCHORING THE CAMERA MOUNT BY THE DISTRICTS SECURITY SYSTEM CONTRACTOR:
  - a). EXPANSION ANCHORS FOR MASONRY, CONCRETE OR GYPSUM.
  - b). DRILL AND/OR TAP FOR STEEL OR SHEET METAL MOUNT.
  - c). SEAL ALL ANCHORS AS A APPROPRIATE FOR INSTALLATION.
  - d). ALL CAMERA MOUNT METHODS AS APPROVED BY THE ENGINEER.
5. 6"x6"x4" DEVICE BOX, WEATHERPROOF.
6. DISTRICT SECURITY SYSTEM CONTRACTOR TO INSTALL AND TERMINATE MAXIMUM OF 4'-6" OF LIQUIDTIGHT FLEX CONDUIT IN ACCORDANCE WITH NEC ARTICLE 350.
7. DISTRICT SECURITY SYSTEM CONTRACTOR TO PROVIDE ALL CABLING.

**SECURITY SYSTEM  
EXTERIOR CORNER MOUNT CAMERA**

