



**NOTES:**

1. ALL GROUND PLATES ARE TO BE FLUSH WITH SURFACE PENETRATED SO AS TO NOT CAUSE A TRIPPING HAZARD. IF FOR ANY REASON THE GROUND PLATE IS NOT INSTALLED FLUSH THE CONTRACTOR SHALL BE REQUIRED AT HIS EXPENSE TO: JACK-HAMMER AND REPOUR CONCRETE; REMOVE AND REINSTALL MASONRY; PAINT; GROUT; RELOCATE EQUIPMENT; PROVIDE TEMPORARY FACILITIES.
2. CONTRACTOR TO SUBMIT GROUNDING ROUTE PLAN AND DETAIL PER SPECS SEC 26 05 26 FOR LVWD APPROVAL.

**EQUIPMENT GROUNDING PLATE - FUTURE USE**

NOT TO SCALE

E02-8 061119

