



NOTES:

- ① CONCEAL CONDUIT IN WALL AT NEW CONSTRUCTION AND AT EXISTING FRAME CONSTRUCTION; SURFACE MOUNT ON INTERIOR FACE AT EXISTING MASONRY.
- ② J-BOX (6" x 6") FOR MOUNTING OF POSITION SWITCH. SWITCH INSTALLATION AND TERMINATIONS BY SECURITY SYSTEM VENDOR. SURFACE MOUNT ON INTERIOR WALL 6" ABOVE FINISHED FLOOR. SEE PLAN FOR CONTINUATION.
- ③ SEE PLAN FOR CONTINUATION.

POSITION SWITCH AT ROLL UP DOOR

NOT TO SCALE

E09-7

033022

