



NOTE:  
ALL CONDUITS AND FITTINGS SHALL BE RIGID GALVANIZED STEEL (RGS) AND ROUTED THROUGH LVAWD PULL BOX.

DESIGNER NOTE:  
SIZE WIRE AND CONDUIT PER SPECIFIC JOB REQUIREMENTS.

TYPICAL CONDUIT, WIRE & CABLE SCHEDULE						
LINE NO.	CONDUIT SIZE	CONDUCTORS	FROM	TO	ROUTE	REMARKS
1	1"	MANUFACTURER SUPPLIED CABLE	TELEMETRY ENCLOSURE	PRESSURE TRANSMITTER	UNDERGROUND	
2	4"	PULL CORD	ELECTRICAL SERVICE PEDESTAL	POWER STUB OUT OR CONNECTION	UNDERGROUND	PER POWER COMPANY REQUIREMENTS
3	2"	PULL CORD	TELEMETRY ENCLOSURE	TELEPHONE STUB OUT OR CONNECTION	UNDERGROUND	PER TELEPHONE COMPANY REQUIREMENTS
4	(2) - 1"	PULL CORD	ELECTRICAL SERVICE PEDESTAL LOCATION	TELEMETRY ENCLOSURE	UNDERGROUND	(1) - RTU CIRCUITS (1) - SPARE W/ PULL CORD
5	2"	(1) - 1/2" HELIAX (2) - #14 (2) - #12	ANTENNA POLE	TELEMETRY ENCLOSURE	UNDERGROUND	(2) - #12 FOR SOLAR PANELS (2) - #14 FOR SOLAR PANELS THEFT PROTECTION