

CLARK COUNTY WATER RECLAMATION DISTRICT GENERAL NOTES

(UPDATED 08/11/2026)

- ALL CONSTRUCTION SHALL CONFORM TO THE DESIGN AND CONSTRUCTION STANDARDS FOR WASTEWATER COLLECTION SYSTEMS, LATEST EDITION AND THE UNIFORM STANDARDS FOR PUBLIC WORKS OFFSITE IMPROVEMENTS, CLARK COUNTY AREA, LATEST EDITION.
- ANY CONFLICTS BETWEEN THESE DOCUMENTS AND THE STANDARDS REFERENCED IN NOTE 1 MUST BE BROUGHT TO THE ATTENTION OF THE ENGINEER OF RECORD PRIOR TO PERFORMING ANY WORK.
- ALL REVISIONS OF THE APPROVED PLANS MUST BE SUBMITTED TO THE CLARK COUNTY WATER RECLAMATION DISTRICT FOR REVIEW AND APPROVAL PRIOR TO PROCEEDING WITH THE WORK. ALL WORK CONSTRUCTED WITHOUT THE APPROVAL OF THE DISTRICT MUST BE REMOVED AT THE CONTRACTORS EXPENSE.
- ALL SANITARY SEWERS SHALL BE PVC SDR-35 SOLID WALL UNLESS OTHERWISE SHOWN.
- ALL SANITARY SEWER MAINS 8-INCHES AND LARGER AND ALL STUBS 8-INCHES AND LARGER ENTIRELY WITHIN THE PUBLIC RIGHT-OF-WAY SHALL BE PUBLIC UNLESS OTHERWISE NOTED. ALL ON-SITE SEWER INFRASTRUCTURE SHALL BE PRIVATE UNLESS OTHERWISE SHOWN. ALL SEWER LATERALS ARE PRIVATE.
- ALL SANITARY SEWER MAINS SHALL BE THE SAME MATERIAL, SIZE, & SLOPE BETWEEN MANHOLES.
- ALL SEWER MAINS SHALL BE IN THEIR OWN TRENCHES. THERE WILL BE NO JOINT TRENCHES ALLOWED.
- THE MINIMUM SLOPES FOR ALL PIPES SHALL BE IN ACCORDANCE WITH THE DESIGN AND CONSTRUCTION STANDARDS.
- ALL SANITARY SEWER MANHOLES MUST BE LOCATED SUCH THAT THEY ARE ACCESSIBLE IN ACCORDANCE WITH THE DESIGN AND CONSTRUCTION STANDARDS.
- A DEBRIS TRAP MUST BE INSTALLED IN THE EXISTING SYSTEM AT THE POINT OF CONNECTION IN ACCORDANCE WITH THE DESIGN AND CONSTRUCTION STANDARDS.
- ALL EXISTING MANHOLE CORROSION PROTECTION SYSTEMS MUST BE RESTORED TO THEIR ORIGINAL CONDITION.
- LOCATOR RIBBON AND MARKER BALLS SHALL BE PLACED ABOVE ALL NEW SEWER MAINS AND LATERALS IN ACCORDANCE WITH THE DESIGN AND CONSTRUCTION STANDARDS.
- ALL EXISTING GRADE MUST BE RAISED TO WITHIN 18-INCHES OF FINAL GRADE PRIOR TO ANY SEWER TRENCHING.
- PRIVATE SANITARY SEWER NOT REVIEWED OR APPROVED BY CCWRD.

I CERTIFY THAT THE ONLY DEVIATIONS FROM THE DESIGN AND CONSTRUCTION STANDARDS THAT ARE APPROVED BY THE CCWRD LISTED BELOW.

• TO BE DETERMINED

XXXXXXXXXXXXX, P.E. XXXXX

DATE

CLARK COUNTY WATER RECLAMATION DISTRICT

DATE

CCWRD PIPES #: XX.XXX

SIGNATURE ON THESE PLANS SHALL NOT BE CONSTRUED TO BE A PERMIT FOR OR AN APPROVAL OF ANY VIOLATION OF CLARK COUNTY WATER RECLAMATION DISTRICT RULES, REGULATIONS, OR DESIGN AND CONSTRUCTION STANDARDS.

REGIONAL TRANSPORTATION COMMITTEE TRANSIT NOTES

(REVISED AUGUST 8, 2024)

- THE CONTRACTOR SHALL NOT BE ALLOWED TO CLOSE MORE THAN TWO CONSECUTIVE BUS STOPS ON THE SAME SIDE OF THE STREET. TEMPORARY BUS STOPS AND BUS STOP AMENITIES SHALL BE IN CONFORMANCE TO THE AMERICANS WITH DISABILITIES ACT (ADA) AND THE ACCESSIBILITY GUIDELINES FOR PEDESTRIAN FACILITIES IN THE PUBLIC RIGHT-OF-WAY (PROWAG) AT ALL TIMES. THE CONTRACTOR SHALL NOTIFY RTC TRANSIT OF PROPOSED BUS STOP CLOSURES AND/OR BUS STOP AMENITY DISRUPTIONS VIA NOTIFYRTCTRANSIT@RTCSNV.COM AT LEAST 7 CALENDAR DAYS PRIOR TO THE START OF WORK. NOTIFICATION OF BUS STOP CLOSURES INVOLVING REMOVAL OF EXISTING AMENITIES SHALL BE PROVIDED TO RTC TRANSIT AT LEAST 10 CALENDAR DAYS PRIOR TO THE START OF WORK.
- TEMPORARY BUS STOPS OR BUS TURNOUTS SHOULD BE CONSIDERED AS AN ALTERNATIVE TO CLOSURES AND ARE SUBJECT TO APPROVAL BY THE RTC. IF A BUS STOP IS TEMPORARILY RELOCATED, TEMPORARY SIGNAGE SHALL BE UTILIZED AT THE TEMPORARY BUS STOP LOCATION AND SHALL REMAIN UNTIL THE TEMPORARY BUS STOP IS REMOVED.
- THE CONTRACTOR SHALL SUBMIT A BUS STOP CLOSURE SCHEDULE TO RTC TRANSIT WITH THE APPROVED TRAFFIC CONTROL PLAN AT LEAST 7 CALENDAR DAYS PRIOR TO THE START OF THE PROJECT. THE BUS STOP CLOSURE SCHEDULE SHALL INCLUDE THE FOLLOWING INFORMATION: BUS STOP ID NUMBERS OF IMPACTED STOPS, NEAREST CROSS STREETS TO IMPACTED STOPS, DURATION OF PROPOSED BUS STOP CLOSURES AND TEMPORARY BUS STOP RELOCATIONS, AND TIMES OF DAY THAT STOPS ARE EXPECTED TO BE IMPACTED BY THE WORK. ALL BUS STOP CLOSURES, TEMPORARY BUS STOPS, AND TEMPORARY BUS TURNOUTS MUST BE APPROVED BY RTC TRANSIT STAFF PRIOR TO THE START OF THE PROJECT.

REGIONAL TRANSPORTATION COMMITTEE
F.A.S.T. NOTES

- CONTRACTOR IS TO MAINTAIN AND KEEP OPERATIONAL ALL EXISTING ITS INFRASTRUCTURE WITHIN THE CONSTRUCTION LIMITS. IF ANY EXISTING ITS INFRASTRUCTURE IS DAMAGED DUE TO CONSTRUCTION, WITHIN THE PROJECT LIMITS, THE CONTRACTOR SHALL IMMEDIATELY CONTACT MR. LONNIE BROWN (RTC/FAST MANAGER TRAFFIC SYSTEMS MAINTENANCE) AT 702-290-1979 CELL OR 702-901-8400 GENERAL.
- IF ANY EXISTING FIBER OPTIC CABLE IS TO BE CUT, SPLICED AND OR PULLED, ALONG OR ADJACENT TO THE PROJECT LIMITS, THE CONTRACTOR IS TO CONTACT MR. LONNIE BROWN TWO (2) WEEKS IN ADVANCE FOR SYSTEM SHUTDOWN COORDINATION.
- CONTRACTOR MUST NOTIFY MR. LONNIE BROWN (RTC/FAST MANAGER TRAFFIC SYSTEMS MAINTENANCE) AT 702-290-1979 CELL OR 702-901-8400 GENERAL OR AT BROWN.L@RTCSNN.COM ONCE ALL PROJECT ITS FIBER OPTIC IS COMPLETE.

CLARK COUNTY TRAFFIC NOTES

(UPDATED 07/08/2025)

- ALL PERMANENT TRAFFIC CONTROL DEVICES CALLED FOR HEREON SHALL BE IN PLACE AND IN FINAL POSITION PRIOR TO ALLOWING ANY PUBLIC TRAFFIC ONTO THE PORTIONS OF THE ROAD(S) BEING IMPROVED HEREUNDER, REGARDLESS OF THE STATUS OF COMPLETION OF PAVING OR OTHER OFF-SITE IMPROVEMENTS CALLED FOR BY THESE PLANS.
- BEFORE ANY WORK IS STARTED IN THE RIGHT-OF-WAY, THE CONTRACTOR SHALL INSTALL ALL ADVANCE WARNING SIGNS FOR THE CONSTRUCTION ZONE. THE CONTRACTOR SHALL INSTALL TEMPORARY GROUND MOUNTED STOP SIGNS AT ALL NEW STREET ENCROACHMENTS INTO EXISTING COUNTY STREETS IMMEDIATELY AFTER FIRST GRADING WORK IS ACCOMPLISHED AND SHALL MAINTAIN SAID SIGNS UNTIL PERMANENT SIGNS ARE INSTALLED.
- ALL CONSTRUCTION SIGNING, BARRICADING AND PAVEMENT MARKINGS SHALL CONFORM TO THE MANUAL OF UNIFORM TRAFFIC CONTROL DEVICES FOR STREETS AND HIGHWAYS, CURRENT EDITION.
- IF THE IMPROVEMENTS NECESSITATE THE OBLITERATION, TEMPORARY OBSTRUCTION, TEMPORARY REM OVAL, OR RELOCATION OF ANY EXISTING TRAFFIC PAVEMENT MARKING, SUCH PAVEMENT MARKING SHALL BE RESTORED OR REPLACED WITH LIKE MATERIALS TO THE SATISFACTION OF THE COUNTY TRAFFIC MANAGER.
- THE DEVELOPER SHALL BE RESPONSIBLE TO PROVIDE AND INSTALL ALL PERMANENT SIGNS SHOWN ON THE PLANS. STREET NAME SIGNS SHALL CONFORM IN THEIR ENTIRETY TO CLARK COUNTY AREA STANDARDS. ALL OTHER SIGNS SHALL BE STANDARD SIZE UNLESS OTHERWISE SPECIFIED ON THE PLANS. ALL SIGN POSTS SHALL BE INSTALLED IN ACCORDANCE WITH CLARK COUNTY AREA STANDARDS. ALL SIGNS SHALL USE CLASS VI SHEETING.
- IF A PROPOSED STREET LIGHT STANDARD IS FIELD LOCATED TO WITHIN FIVE (5') FEET OF ANY SIGN SHOWN HEREON TO BE MOUNTED ON A SIGN POST, CHANGE SIGN MOUNTING TO ONE ON THE STREETLIGHT STANDARD.
- PRIOR TO CONSTRUCTION, THE STREET SIGN CONTRACTOR SHALL OBTAIN STREET NAMES AND BLOCK NUMBERING FROM THE CURRENT PLANNING DIVISION OF THE DEPARTMENT OF COMPREHENSIVE PLANNING.
- ALL TRAFFIC SIGNAL POLE ASSEMBLIES, STEEL PEDESTAL FOR CABINETS AND STREET LIGHT POLES SHALL BE GALVANIZED PER ASTM A.123.
- ALL STREET LIGHTING INSTALLATIONS SHALL CONFORM TO THE UNIFORM STANDARD DRAWINGS AND THE UNIFORM STANDARD SPECIFICATIONS FOR PUBLIC WORKS' CONSTRUCTION OFF-SITE IMPROVEMENTS CLARK COUNTY AREA, NEVADA, LATEST EDITION OF EACH EXCEPT AS NOTED ON THE STREET LIGHTING PLANS AND LED LUMINAIRES. REFER TO CLARK COUNTY PUBLIC WORKS QUALIFIED PRODUCTS LIST "QPL" FOR LED LUMINAIRES. QPL CAN BE FOUND ONLINE AT [HTTPS://WWW.CLARKCOUNTYNV.GOV/GOVERNMENT/DEPARTMENTS/PUBLIC_WORKS_DEPARTMENT/LED-QUALIFIED-PRODUCT-LIST-QPL](https://www.clarkcountynv.gov/government/departments/public_works_department/led-qualified-product-list-qpl)
- THE FOLLOWING CLARK COUNTY UNDERGROUND FACILITIES MAY BE LOCATED IN YOUR PROJECT AREA: STREET LIGHTING, TRAFFIC SIGNALS, AND FREEWAY AND ARTERIAL SYSTEM OF TRANSPORTATION (F.A.S.T.) INTERCONNECT CABLE. YOU MUST CONTACT CLARK COUNTY TRAFFIC MANAGEMENT DIVISION, OPERATIONS UNIT AT 455-6000 FOR LOCATIONS AT LEAST 48 HOURS PRIOR TO WORKING IN THE AREA. CLARK COUNTY IS NOT A MEMBER OF "CALL BEFORE YOU DIG" (UNDERGROUND SERVICE ALERT), AND A CALL TO THAT ORGANIZATION DOES NOT RELIEVE YOU OF LIABILITY FOR CLARK COUNTY FACILITIES.
- F.A.S.T. INTERCONNECT CABLE POLICY IS IN EFFECT. INTERCONNECT CABLE MUST BE MAINTAINED AT ALL TIMES. DEVELOPER/CONTRACTOR SHALL PROVIDE TEMPORARY OVERHEAD INTERCONNECT CABLE WHILE PERMANENT CABLE IS BEING RELOCATED. TEMPORARY AERIAL INSTALLATION MUST BE ACCEPTABLE TO THE COUNTY TRAFFIC MANAGER AND TO F.A.S.T. ANY DAMAGE TO THIS CABLE IS DEEMED IN EMERGENCY BY F.A.S.T., CITY OF LAS VEGAS, CLARK COUNTY AND NDOT AND MUST BE REPAIRED IMMEDIATELY TO F.A.S.T. ACCEPTANCE. \$2,500 PER DAY DAMAGES MAY BE ASSESSED AFTER 24 HOURS HAS ELAPSED FROM TIME OF BREAK OR DAMAGE.
- ALL NEW OR REPLACEMENT TRAFFIC SIGNAL LOOPS SHALL BE INSTALLED USING CABLE-IN-DUCT WIRING, SHALL HAVE INDEPENDENT LEAD-IN WIRES FOR EACH LOOP FROM THE CONTROLLER TO THE PULL-BOX, AND EACH LEAD-IN SHALL BE INDIVIDUALLY TAGGED.
- TRAFFIC SIGNAL PEDESTRIAN HEADS SHALL BE THE LED TYPE.
- ELECTRICAL POWER SERVICE POINT LOCATION(S) FOR STREET LIGHTING AND TRAFFIC SIGNALS MUST BE INDICATED ON THE PLANS. IF CONNECTING TO AN EXISTING CIRCUIT, INDICATE LOCATION OF EXISTING SERVICE POINT FOR EACH CIRCUIT.
- WHEN STREETLIGHTS ARE TO BE CONNECTED TO AN EXISTING CIRCUIT, THE ENGINEER MUST CERTIFY THAT THE EXISTING CIRCUIT IS CAPABLE OF HANDLING THE ADDITIONAL CIRCUIT LOAD.
- CLARK COUNTY RESERVES THE RIGHT TO REJECT STREET LIGHT AND TRAFFIC SIGNAL POLES AND ASSEMBLIES WHICH HAVE A "STRIPED" APPEARANCE.
- TWO WEEKS PRIOR TO BEGINNING OF CONSTRUCTION, MODIFICATION OR RELOCATION OF ANY TRAFFIC SIGNAL SYSTEM, WRITTEN NOTICE SHALL BE SUBMITTED TO THE CLARK COUNTY TRAFFIC MANAGEMENT DIVISION OF THE DATE THAT WORK WILL BEGIN.
- THREE (3) NORMAL WORKING DAYS PRIOR TO TURN-ON OR COMPLETION OF MODIFICATION(S) TO A TRAFFIC SIGNAL SYSTEM, WRITTEN NOTICE SHALL BE SUBMITTED TO THE CLARK COUNTY TRAFFIC MANAGEMENT DIVISION THAT WORK IS BEING COMPLETED AND THE PROPOSED DATE OF COMPLETION.

DEVIATIONS FROM STANDARDS

THERE ARE NO DEVIATIONS FROM APPLICABLE STANDARDS.

DEPARTMENT OF PUBLIC WORKS DEVELOPMENT REVIEW
CONSTRUCTION NOTES

(UPDATED 07/08/2025)

- INSPECTIONS ARE REQUIRED. CALL 24 HOURS IN ADVANCE (702) 455-4610. THE PERMIT, APPROVED PLANS, AND BARRICADE PLANS FOR THIS WORK MUST BE ON THE JOB SITE AT ALL TIMES.
- EXACT LOCATION OF ALL SAW-CUT LINES SHALL BE DETERMINED IN THE FIELD BY A CLARK COUNTY INSPECTOR.
- CURB AND GUTTER WITH A GRADE OF LESS THAN 4/10 OF ONE PERCENT SHALL BE CONSTRUCTED BY FORMING. EACH JOINT SHALL BE CHECKED FOR GRADE PRIOR TO CONSTRUCTION AND WATER TESTED AS SOON AS POSSIBLE AFTER CONSTRUCTION.
- FINAL ASPHALTIC CONCRETE (AC) PAVEMENT SURFACES SHALL BE ONE-HALF (1/2") INCH ABOVE THE LIP OF THE GUTTER (INCLUDING OPEN GRADE).
- ALL OFF-SITE IMPROVEMENT CONSTRUCTION SHALL CONFORM TO THE UNIFORM STANDARD SPECIFICATIONS AND STANDARD DRAWINGS CLARK COUNTY AREA NEVADA AND CLARK COUNTY SUPPLEMENT TO UNIFORM STANDARD DRAWINGS AND SPECIFICATIONS, LATEST REVISION EXCEPT FOR LUMINAIRES. REFER TO CLARK COUNTY PUBLIC WORKS QUALIFIED PRODUCTS LIST "QPL" FOR LED LUMINAIRES. QPL CAN BE FOUND ONLINE [HTTPS://WWW.CLARKCOUNTYNV.GOV/GOVERNMENT/DEPARTMENTS/PUBLIC_WORKS_DEPARTMENT/LEDQUALIFIED-PRODUCT-LIST-QPL](https://www.clarkcountynv.gov/government/departments/public_works_department/ledqualified-product-list-qpl)
- PRIVATE STREETS CURB & GUTTER AND VALLEY GUTTERS REFLECTED ON THESE PLANS ARE TO BE INSPECTED BY A CLARK COUNTY INSPECTOR.
- WHEEL CHAIR RAMPS SHALL BE CONSTRUCTED IN EACH QUADRANT OF AN INTERSECTION PER STANDARD DRAWING 235. EXACT LOCATION OF RAMPS SHALL BE DETERMINED IN THE FIELD BY A CLARK COUNTY INSPECTOR.
- PROPER SIGNS, BARRIERS, BARRICADES AND LIGHTS SHALL BE PLACED AND MAINTAINED IN ACCORDANCE WITH THE LATEST "MANUAL OF UNIFORM TRAFFIC CONTROL DEVICES FOR STREETS AND HIGHWAYS." TRAFFIC, SCHOOL, OR STREET SIGNS OF ANY KIND ARE NOT TO BE MOVED FOR ANY REASON WITHOUT FIRST COORDINATING WITH THE DEPARTMENT OF PUBLIC WORKS INSPECTOR AT (702)455-4610.
- THIS PLAN DOES NOT AUTHORIZE CLOSURE OF ANY ROAD OR STREET.
- NO OPEN TRENCH SHALL BE ALLOWED ACROSS ANY STREET OR WITHIN TEN (10') FEET OF ANY TRAVEL-WAY, EXCEPT WHEN WORK IS IN ACTUAL PROGRESS. AREAS COVERED BY ACCEPTABLE STEEL PLATE ARE NOT TO BE CONSTRUED AS A TRENCH. NO OPEN TRENCH IS PERMITTED IN EXCESS OF 500 FEET OR LENGTH NECESSARY TO ACCOMMODATE PIPE INSTALLATION IN A SINGLE DAY, WHICHEVER IS GREATER. ALL TRENCH CROSSINGS AND BACKFILL SHALL MEET THE STANDARD SPECIFICATION UNLESS OTHERWISE STATED.
- A TEMPORARY PATCH IS TO BE IN PLACE AT THE END OF EACH WORK DAY WHERE THE BACKFILL IN THE TRENCH HAS BEEN COMPLETED AND PRIOR TO OPENING THE WORK AREA BACK TO TRAFFIC AND IS TO BE MAINTAINED BY THE PERMITTEE. A PERMANENT PATCH IS TO BE IN PLACE WITHIN THIRTY (30) DAYS AFTER THE INSTALLATION OF THE TEMPORARY PATCH.
- COMPACTION TESTS ARE REQUIRED.

CLARK COUNTY FIRE DEPARTMENT GENERAL NOTES

(UPDATED 01/01/2026)

GENERAL

- ALL WORK SHALL BE DONE IN STRICT ACCORDANCE WITH THE CLARK COUNTY FIRE CODE AS AMENDED, THE UNIFORM DESIGN AND CONSTRUCTION STANDARDS (UDACS) AS ADOPTED BY THE WATER PURVEYOR AND THE CURRENTLY ADOPTED EDITION OF NFPA 24.
- FIRE HYDRANTS AND WATER SUPPLIES FOR FIRE PROTECTION SHALL BE INSTALLED, INSPECTED BY FIRE PREVENTION AND IN SERVICE PRIOR TO AND DURING THE TIME OF CONSTRUCTION IN ACCORDANCE WITH SECTION 3307 OF THE IFC, AS AMENDED. FIRE HYDRANTS SHALL BE WITHIN 300 FEET OF COMBUSTIBLE MATERIALS.
- IF DURING CONSTRUCTION IT BECOMES NECESSARY TO CLOSE ANY CONTROL VALVE OR PLACE A HYDRANT OUT OF SERVICE, APPROVAL SHALL BE OBTAINED FROM THE CLARK COUNTY FIRE PREVENTION PRIOR TO PLACING THE HYDRANT OUT OF SERVICE.

FIRE HYDRANTS

- FIRE HYDRANTS SHALL BE INSTALLED IN ACCORDANCE WITH THE CLARK COUNTY FIRE CODE AS AMENDED, THE UNIFORM DESIGN AND CONSTRUCTION STANDARDS (UDACS) AS ADOPTED BY THE WATER PURVEYOR AND THE CURRENTLY ADOPTED EDITION OF NFPA 24. FIRE HYDRANTS SHALL BE MAINTAINED IN ACCORDANCE WITH NFPA 25 AND KEPT IN AN OPERATIVE CONDITION WITH THE REQUIRED WATER SUPPLY.
- MANUFACTURER AND MODEL OF FIRE HYDRANTS SHALL CONFORM TO THE APPROVED MATERIALS LIST OF THE WATER PURVEYOR.
- HYDRANTS SHALL BE INSTALLED WITH THEIR PUMPER OUTLET NOZZLE (STEAMER CONNECTION) FACING THE FIRE ACCESS ROAD. A 3-FOOT CLEAR SPACE SHALL BE MAINTAINED AROUND THE CIRCUMFERENCE OF FIRE HYDRANTS. WHERE HYDRANTS ARE SUBJECT TO IMPACT BY MOTOR VEHICLES, GUARD POSTS (PIPE BOLLARDS) SHALL BE INSTALLED IN ACCORDANCE WITH SECTION 312.
- PUBLIC HYDRANTS SHALL BE PAINTED SAFETY YELLOW AND PRIVATE HYDRANTS SHALL BE PAINTED RED.
- FIRE HYDRANTS SHALL BE LOCATED 4 TO 7 FEET FROM BACK OF CURB.
- PAINTING OF CURBS AND/OR ASPHALT AREAS ADJACENT TO HYDRANTS SHALL BE COMPLETED BY THE INSTALLER PRIOR TO BOND RELEASE INSPECTION. A COAT OF EXTERIOR INDUSTRIAL GRADE SAFETY RED ENAMEL SHALL BE APPLIED FOR A MINIMUM OF 30 FEET (15 FEET ON EACH SIDE OF THE HYDRANT).
- HYDRANT LOCATIONS SHALL BE MARKED BY MEANS OF A BLUE REFLECTIVE PAVEMENT MARKER INSTALLED IN THE CENTER OF THE FIRE ACCESS DRIVE LANE NEAREST TO THE HYDRANT.

FIRE DEPARTMENT CONNECTIONS

- FIRE DEPARTMENT CONNECTIONS SHALL BE LOCATED WITHIN 100 FEET OF A FIRE HYDRANT AS MEASURED BY AN APPROVED UNOBSTRUCTED ROUTE. AN APPROVED ROUTE IS DEFINED AS AN UNOBSTRUCTED PATH OF TRAVEL ON WHICH HOSE CAN EASILY BE LAID.
- FIRE DEPARTMENT CONNECTIONS SHALL BE LOCATED ON THE FIRE DEPARTMENT ACCESS SIDE OF BUILDINGS, FULLY VISIBLE AND RECOGNIZABLE FROM THE ACCESS ROAD OR NEAREST POINT OF FIRE DEPARTMENT VEHICLE ACCESS (FIRE LANE) OR AS OTHERWISE APPROVED BY THE FIRE CODE OFFICIAL.
- FIRE DEPARTMENT CONNECTIONS SHALL NOT BE CLOSER THAN 3 FEET TO ANY DOOR OR WINDOW OPENING AND SHALL NOT BE OBSTRUCTED BY TREES, SHRUBS, PARKING SPACES, ETC.
- FIRE DEPARTMENT CONNECTIONS SHALL BE LOCATED NOT LESS THAN 18 INCHES AND NOT MORE THAN 48 INCHES ABOVE THE LEVEL OF THE ADJACENT GRADE OR ACCESS LEVEL.

UNDERGROUND PIPING & VALVES

- UNDERGROUND PIPING SHALL HAVE A MINIMUM WORKING PRESSURE OF 150 PSI (CLASS 235). UNDERGROUND PIPING CONNECTED TO A FIRE PUMP OR A FIRE DEPARTMENT CONNECTION (FDC) SHALL HAVE A MINIMUM WORKING PRESSURE OF 200 PSI (CLASS 305).
- FOR PRIVATE FIRE SERVICE MAINS TWO SOURCES OF WATER SUPPLY ARE REQUIRED WHENEVER 4 OR MORE FIRE HYDRANTS AND/OR FIRE SPRINKLER LEAD-INS ARE INSTALLED ON A SINGLE SYSTEM. WATER SYSTEMS UNDER THE PURVIEW OF THE LAS VEGAS VALLEY WATER DISTRICT SHALL CONFORM TO THE LAS VEGAS VALLEY WATER DISTRICT RULES.
- FOR PRIVATE FIRE SERVICE MAINS SECTIONAL CONTROL VALVES SHALL BE INSTALLED SO THAT NO MORE THAN 2 FIRE HYDRANTS AND/OR FIRE SPRINKLER IN BUILDING RISERS (LEAD-INS) CAN BE OUT OF SERVICE DUE TO A BREAK IN A WATER MAIN. WATER SYSTEMS UNDER THE PURVIEW OF THE LAS VEGAS VALLEY WATER DISTRICT SHALL CONFORM TO THE LAS VEGAS VALLEY WATER DISTRICT RULES.
- ALL PIPING AND VALVES SUPPLYING FIRE SPRINKLER SYSTEMS SHALL BE PROTECTED FROM FREEZING WHEN EXPOSED TO TEMPERATURES LESS THAN 40°F. FREEZE PROTECTION SHALL BE APPROVED BY CLARK COUNTY FIRE PREVENTION AND BE DURABLE AND PERMANENT.
- ALL REQUIRED HYDROSTATIC TESTING AND FLUSHING OF THE PRIVATE FIRE SERVICE MAIN OR UNDERGROUND FIRE SPRINKLER/STANDPIPE WATER SUPPLY PIPING SHALL BE PERFORMED IN THE PRESENCE OF CLARK COUNTY FIRE PREVENTION STAFF. THE PIPING JOINTS SHALL BE UNCOVERED UNTIL INSPECTED. THE INSTALLING CONTRACTOR SHALL FURNISH A "CONTRACTOR'S MATERIAL AND TESTING CERTIFICATE" (CM&T) COUNTERSIGNED BY THE PROPERTY OWNER OR REPRESENTATIVE. THE CM&T SHALL BE FILLED OUT COMPLETELY WITH THE INSPECTOR'S INITIALS, WITNESSING EACH TEST. A COPY OF THE UNDERGROUND FLUSH AND HYDROSTATIC TESTING DOCUMENTATION SHALL BE ON-SITE AND SIGNED PRIOR TO THE CONNECTION OF THE UNDERGROUND WATER SUPPLY TO THE FIRE SPRINKLER SYSTEM.

GATES

- SHOP DRAWINGS FOR ALL GATES AND MOTORIZED OPENERS SERVING FIRE DEPARTMENT ACCESS ROADS SHALL BE SUBMITTED SEPARATELY UNDER A SEPARATE PERMIT FOR REVIEW BY THE CLARK COUNTY BUILDING DEPARTMENT AND FIRE PREVENTION AND RECEIVE APPROVAL PRIOR TO THEIR INSTALLATION.

FIRE APPARATUS ACCESS ROADS

- SPEED BUMPS AND/OR SPEED HUMPS SHALL NOT BE PERMITTED WITHIN THE REQUIRED WIDTH OF FIRE APPARATUS ACCESS ROADS.

EXCEPTIONS:

- SPEED HUMPS ARE ALLOWED ON PRIVATE FIRE APPARATUS ACCESS ROADS SERVING COMMERCIAL AND INDUSTRIAL BUILDINGS WHEN APPROVED BY THE FIRE CODE OFFICIAL.
- RUMBLE STRIPS ARE ALLOWED ON PRIVATE FIRE APPARATUS ACCESS ROADS SERVING RESIDENTIAL, COMMERCIAL AND INDUSTRIAL BUILDINGS WHEN APPROVED BY THE FIRE CODE OFFICIAL.
- A MAXIMUM OF SIX SINGLE FAMILY HOMES CONSTRUCTED IN ACCORDANCE WITH THE IRC MAY BE SITUATED ON A 25-FOOT-WIDE STREET (STUB STREET) HAVING A MAXIMUM LENGTH OF 150 FEET. THE MINIMUM WIDTH SHALL BE 25 FEET MEASURED FROM BACK-OF-CURB TO BACK-OF-CURB AND ON-STREET PARKING SHALL BE PROHIBITED ON SUCH STUB STREETS.
- FIRE APPARATUS ACCESS ROADS SHALL BE DESIGNED AND MAINTAINED TO SUPPORT THE IMPOSED LOADS OF FIRE APPARATUS, WITH A MINIMUM VEHICLE LOAD OF 33,000 POUNDS PER AXLE, AND SHALL BE SURFACED AND PAVED SO AS TO PROVIDE ALL-WEATHER DRIVING CAPABILITIES.
- FIRE APPARATUS ACCESS ROADS INCLUDING ELEVATED PORTIONS SHALL BE DESIGNED WITH A GROUND BEARING CAPACITY NOT LESS THAN 75 PSI OVER THE GROUND CONTACT AREA.


SIGNATURE/STAMP: _____ DATE: _____

APPROVAL OF THESE PLANS SHALL NOT BE CONSTRUED TO BE A PERMIT FOR, OR AN APPROVAL OF, ANY VIOLATION OF ANY OF THE PROVISIONS OF THE STATE OR COUNTY LAWS.


FIRE FLOW = _____ GPM AT 20PSI RESIDUAL.

CLV DWG # _____

LAS VEGAS VALLEY
WATER DISTRICT™



VERIFY SCALE



BAR REPRESENTS
ONE AND ONE-HALF
INCHES ON ORIGINAL

XXXXXXXXXXXXXXXXXXXX
XXXXXXXXXXXXXXXXXXXX

SCALE
HORIZ SCALE
1"=XX'
VERT SCALE
1"=XX'

LAS VEGAS VALLEY
WATER DISTRICT™

1001 S. VALLEY VIEW BLVD, LAS VEGAS, NV 89113



DRAWN BY:

CHECKED BY:

PROJECT: XXXXX

COMMIT: XXXX

DRAWING/NUMBER

XXXXXX

SHEET XX OF XXX

REVISIONS: