

NOTES FOR PAVED AND UNPAVED AREAS

PL02-4 072315

1. REFERENCES:
UNIFORM STANDARD SPECIFICATIONS FOR PUBLIC
WORKS CONSTRUCTION OFF-SITE IMPROVEMENTS CLARK
COUNTY AREA NEVADA, LATEST EDITION.

INTERAGENCY QUALITY ASSURANCE COMMITTEE (IQAC)
2. SEE SPECS SEC 31 20 00 FOR ACCEPTABLE METHODS OF
COMPACTION.
3. TRENCH EXCAVATION: COMPLY WITH THE CURRENT
REGULATIONS AS DETERMINED BY NEVADA
OCCUPATIONAL SAFETY AND HEALTH ADMINISTRATION.
4. DURING CONSTRUCTION 24" MINIMUM COVER MUST BE
MAINTAINED FROM TOP OF PIPE TO GRADE.
5. MINIMUM COVER IS REFERENCED TO FUTURE FINISHED
FINAL GRADES UNLESS OTHERWISE SHOWN ON PROFILE
DRAWINGS.
6. SUPPORT PIPE AND FIBER OPTIC CONDUITS (IF
REQUIRED) WITH SANDBAGS AND SPOT LOAD AS
REQUIRED DURING INSTALLATION OF CLSM IN PIPE ZONE
AND PIPE BEDDING AREAS.
7. DIAGONAL PAVEMENT REPLACEMENT IS NOT PERMITTED.
8. FOG SEAL (SEAL COAT) ALL DENSE GRADE PAVEMENT
REPLACEMENT SECTIONS.