

NOTES FOR PAVED AND UNPAVED AREAS

PL02-4 072315

1. REFERENCES:
UNIFORM STANDARD SPECIFICATIONS FOR PUBLIC WORKS
CONSTRUCTION OFF-SITE IMPROVEMENTS CLARK COUNTY
AREA NEVADA, LATEST EDITION.

INTERAGENCY QUALITY ASSURANCE COMMITTEE (IQAC)
2. SEE SPECS SEC 31 20 00 FOR ACCEPTABLE METHODS
OF COMPACTION.
3. TRENCH EXCAVATION: COMPLY WITH THE CURRENT
REGULATIONS AS DETERMINED BY NEVADA OCCUPATIONAL
SAFETY AND HEALTH ADMINISTRATION.
4. DURING CONSTRUCTION 24" MINIMUM COVER MUST BE
MAINTAINED FROM TOP OF PIPE TO GRADE.
5. MINIMUM COVER IS REFERENCED TO FUTURE FINISHED
FINAL GRADES UNLESS OTHERWISE SHOWN ON PROFILE
DRAWINGS.
6. SUPPORT PIPE AND FIBER OPTIC CONDUITS (IF REQUIRED)
WITH SANDBAGS AND SPOT LOAD AS REQUIRED DURING
INSTALLATION OF CLSM IN PIPE ZONE AND PIPE BEDDING
AREAS.
7. DIAGONAL PAVEMENT REPLACEMENT IS NOT PERMITTED.
8. FOG SEAL (SEAL COAT) ALL DENSE GRADE PAVEMENT
REPLACEMENT SECTIONS.